TECNO CANAPA BIOEDILIZIA

CBB04

SPECIFICATION ITEM

04/06/2026

INTERIOR LINING WALL MADE OF SINGLE GYPSUM FIBERBOARD PANEL AND HEMP FIBER PANELS BIO BETON® PRONTO

ITEM DESCRIPTION

Supply and installation of an insulating interior lining wall made with a single Fermacell gypsum fiberboard panel (μ=13), thickness 12.5 mm, on a wooden batten substructure fitted into horizontal galvanized sheet-metal "U" guides fixed to the floor and ceiling. The panels shall be staggered relative to one another and the joints between panels properly filled.
Supply and installation of Bio Beton® Pronto biocomposite made of coarse hemp shiv, natural dolomitic binder and probiotic additive, thickness 4 cm (density 200 kg/m³ - thermal conductivity 0.053 W/mK - μ 4.5), inserted in the cavity between the panel and the existing substrate.
Supplied pre-mixed in 2 m³ big bags. Manual installation using wheelbarrows.
Item inclusive of labor, materials and transport.
Gross measurement, openings not deducted (Vpp), up to 4.5 m². For larger openings, a surface area of 4.5 m² will be counted.

- Excluding wall reinforcements.
- Excluding skim coat.
- Excluding painting.
- Excluding layout markings and drawings.

NOTES

Tecnocanapa · Senini Srl reserves the right to modify and/or update the data provided in this document.
The updated version is available on the website https://tecnocanapa-bioedilizia.it/ .
This document cancels and supersedes any previous version.